

Addendum:

East Macon Park Baseball Fence

Base Bid:

Description: Demolition and Installation of Field # 1 Baseball Field to included replacing Dugout roofs.

- Minimum 4" Schedule 40 Backstop Post
- Backstop 10' height with 4' Angle
- 2" Schedule 40 Bottom Rail to secure fence bottom
- 2.5" Schedule 40 Terminal
- 2.5" Schedule 40 Top Rail
- Galvanized Fence
- 7 gauge Tension Wire

Description: Demolition and Installation of Field # 2 and # 3 with the following exception: Prime and Paint the existing Backstops and Dugout Post; and leave Dugout Roof.

- 2" Schedule 40 Bottom Rail to secure fence bottom
- 2.5" Schedule 40 Terminal
- 2.5" Schedule 40 Top Rail
- Galvanized Fence
- 7 gauge Tension Wire

Option 1: Black Fence

Description: Demolition and Installation of Field # 1 Baseball Field to included replacing Dugout roofs.

- Minimum 4" Schedule 40 Backstop Post
- Backstop 10' height with 4' Angle
- 2" Schedule 40 Bottom Rail to secure fence bottom
- 2.5" Schedule 40 Terminal
- 2.5" Schedule 40 Top Rail
- Black Coated Fence with 9 gauge black vinyl with at least a 6 gauge wire
- 7 gauge Tension Wire

Description: Demolition and Installation of Field # 2 and # 3 with the following exception: Prime and Paint the existing Backstops and Dugout Post; and leave Dugout Roof.

- 2" Schedule 40 Bottom Rail to secure fence bottom
- 2.5" Schedule 40 Terminal
- 2.5" Schedule 40 Top Rail
- Black Coated Fence with 9 gauge black vinyl with at least a 6 gauge wire
- 7 gauge Tension Wire