

2016 LMIG

Full Depth Reclamation & Deep Patch with Overlay Bid Schedule

The quantities listed are an approximate estimate of the materials required to complete the full depth reclamation and deep patch with overlay resurfacing projects:

BASE BID: (FULL DEPTH RECLAMATION, FDR)

Former Bibb County Government:

Kentucky Downs Drive, Bowman Road, Yorkshire Way, Regina Drive

(DEEP PATCHING AND OVERLAY, DP&O)

Former City of Macon Government:

Kingsley Drive, Brookhaven Road, Monroe Street, Friar Road, Clifton Drive, Date Avenue, Log Cabin Drive, Castlewood Drive, James Street, Dapleton Drive, Canterbury Road, Jordan Avenue, Walker Road, Tech Drive, Grayson Avenue, Westbury Drive, Ebenezer Church Road,

Former Bibb County Government:

Kings Park Circle, Cambridge Way, Misty Valley Drive, Bishop Road

Former Bibb County Government: (FDR and Deep Patch with Overlay)

Quantity	Unit	Item	Unit Price	Total
24,067	SY	Reclaimed base course	_____	_____
2340	TONS	Milling	_____	_____
512	TONS	Portland cement	_____	_____
3611	GAL	Bituminous Prime	_____	_____
1360	GAL	Bituminous Tack	_____	_____
2277	TONS	12.5 mm Superpave Asphalt	_____	_____

1200	SY	Roadway Patching	_____	_____
2334	TONS	9.5 mm Superpave Asphalt	_____	_____
27	EA	Install Furnished Sewer Manhole & water valve risers, 1”	_____	_____
400	CY	GABC needed for additional sub-grade excavation	_____	_____
1	EA	Traffic Control loop	_____	_____
1.4	MILE	Striping (paint)	_____	_____
4	EA	Pavement markings (arrows, paint)	_____	_____
165	LF	Pavement markings (cross walks, paint)	_____	_____
4	EA	Pavement markings (stop bars, paint)	_____	_____
210	LF	Pavement markings (hatching, paint)	_____	_____

Former City of Macon Government:

<u>Quantity</u>	<u>Unit</u>	<u>Item</u>	<u>Unit Price</u>	<u>Total</u>
5094	SY	Roadway Patching	_____	_____
3512	GAL	Bituminous Tack	_____	_____
4994	TONS	Milling	_____	_____
5979	TONS	9.5 mm Superpave Asphalt	_____	_____
121	EA	Install furnished sewer manhole & water valve risers, 1”	_____	_____
750	CY	GABC needed for additional sub-grade excavation	_____	_____

7	EA	Traffic Control loop	_____	_____
3.41	MILE	Striping (paint)	_____	_____
7	EA	Pavement markings (arrows, paint)	_____	_____
670	LF	Pavement markings (cross walks, paint)	_____	_____
19	EA	Pavement markings (stop bars, paint)	_____	_____
490	LF	Pavement markings (hatching, paint)	_____	_____