

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0139 Smith

Dollie Smith
4090 Marse Allen Road
Macon, Georgia 31206
Home Phone: 478 788 4589

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Contractor shall also carry worker's compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements concerning warranty.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing On Chimneys**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

***** **APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF** *****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0140 Rainey

Benjamin & Annie Rainey
4181 Marion Avenue
Macon, Georgia 31206
Home Phone: 478 784 4462

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Contractor shall also carry worker’s compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____%

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0141 Hike

Connie Hike
346 Hortman Avenue
Macon, Georgia 31204
Cell Phone: 478 361 1189

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner and Program Administrator. Refer to the project contract for specific requirements concerning warranty.

Attachment “B”
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection before covering.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing on Chimneys and @ Porch Gable**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF *****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0142 Isabell

Kathy Isabell
3359 Toole Drive
Macon, Georgia 31204
Home Phone: 478 742 2525 Cell Phone: 478 461-4426

Wednesday, June 14, 2017
Location
Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs, and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

***** APPLY DRIP EDGE TO PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0143 Swint

Patricia Swint
3113 Mary Drive
Macon, Georgia 31204
Cell Phone: 478 319 8199

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing on Chimneys**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

*****APPLY DRIP EDGE TO PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____%

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0144 Davis

Betty Davis
3496 Charleston Circle
Macon, Georgia 31204
Cell Phone: 478 972 4986

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment “B”
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE TO PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0145 Rivers

Debra Rivers
2489 Second Street
Macon, Georgia 31206
Cell Phone: 478 283 8935

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment “B”
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.0975 **Install New Modified Asphalt Roof Membrane @ FRONT PORCH**

Install new 95 lb. asphalt roofing/waterproofing membrane material. Roof covering material shall be "NORDPOLY 4M" modified asphalt roofing membrane or program approved equal.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing on Chimneys**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

***** APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

Attachment "B"
Guidelines, Specifications and Cost Summary

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____%

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0146 Holmes

Burnett Holmes
430 Fort Hill Street
Macon, Georgia 31217
Home Phone: 478 741 9628 Cell Phone: 478 461 5700

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment “B”
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

20.0075 **Trim Tree Overhanging Roof**

Trim tree limbs overhanging roof so that a vertical clearance of about 15 feet exists between the roof Plane and any remaining tree limbs. Clean leaves and debris from roof. Remove debris to legal dump site.

35.0250 **Repair The Cornice @ RIGHT & REAR**

Replace severely defective, rotten and missing cornice components including fascia boards, soffit boards, frieze boards and rafter tails. New material to match remaining material as closely as possible.

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace Up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least ½" into masonry units of chimneys. Program Administrator will select color.

35.0975 **Install New Modified Asphalt @ PORCH AREA**

Install new 95 lb. asphalt roofing/waterproofing membrane material. Roof covering material shall be "NORDPOLY 4M" modified asphalt roofing membrane or program approved equal.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.1125 **Install Metal Flashing on Chimneys**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

***** APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0147 Moore

Sharon Moore
2612 Tredway Drive
Macon, Georgia 31211
Home Phone: 478 745 3255 or Cell Phone: 478 318 1259

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be of high quality, 2) be installed in accordance with manufacturer’s specs and, 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for Compliance Inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing on Chimney**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

*****APPLY DRIP EDGE TO THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor	_____
Overhead and Profit @ _____%	_____
Total Cost	_____

Attachment “B”
Guidelines, Specifications and Cost Summary

Work Write-Up
2017 0148 Wilkerson

Ann Wilkerson
955 Quinlan Drive
Macon, Georgia 31206
Home Phone: 478 788 2530 or Cell Phone: 478 501 5297

Wednesday, June 14, 2017

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker’s Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer’s specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment “B”
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection before covering.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____