

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0164 Cabey

Cabey, Fernella
3203 Kings Park Circle
Macon, Georgia 31217
Cell Phone: 478 501 3143

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Contractor shall also carry worker's compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements concerning warranty.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0165 Pitts

Pitts, Nancy
711 Forest Lake Drive South
Macon, Georgia 31210
Home Phone: 478 254 2568

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Contractor shall also carry worker's compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0225 **Install Fascia Board over End of Rafter Tails**

Install new 2" x 4" pine sub-fascia and 3/4" thick #2 spruce fascia board to cover the ends of the rafter tails. Replace severely defective, rotten and missing rafter tails.

30.0975 **Prime Bare Wood**

Apply quality primer with 10 year manufacturer warranty to all bare wood on exterior of house. Primer to be applied using brush—spraying is not permitted. Primer to have a color similar to that of paint on house.

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0166 Freeman

Freeman-Willis, Betty
4276 Robinson Circle
Macon, Georgia 31204
Home Phone: 478 477 4435

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner and Program Administrator. Refer to the project contract for specific requirements concerning warranty.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection before covering.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____%

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0167 Tanner

Tanner, Mary Frances
2096 Neal Avenue
Macon, Georgia 31204
Cell Phone: 478 955 5135

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs, and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

35.1125 **Install Metal Flashing on Chimneys**

Properly install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimney. Aluminum flashing is not permitted.

***** APPLY DRIP EDGE AROUND THE PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0168 McFadden

McFadden, Janet
4724 Bishop Rd
Macon, Georgia 31206
Home Phone: 478 201 0413

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01.0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01.0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.0975 **Install New Modified Asphalt @ Rear Porch**

Install new 95lb. asphalt roofing/waterproofing membrane material Roof covering material shall be "NORDPOLY 4M" modified asphalt roofing membrane or program approved equal.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0169 Moss

Moss, Dorothy
4514 Wilson Rd
Macon, Georgia 31206
Home Phone: 478 471 9465 Cell Phone: 478 335 8977

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0170 Hunter

Hunter, Evelyn
4814 Brookhaven Rd
Macon, Georgia 31206
Home Phone: 478 747 6739

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Materials shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

***** APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____ % _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0171 Archer

Archer, Rose
5044 Massey Rd
Macon, Georgia 31206
Home Phone: 478 297 3231

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace Up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

***** **APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*******

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0172 Ball

Ball, Mattie
4334 Ayers Rd
Macon, Georgia 31210
Home Phone: 478 474 8287 Cell Phone: 478 262 5713

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be of high quality, 2) be installed in accordance with manufacturer's specs and, 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0525 **Replace up to 40% of Roof Decking**

Replace up to 40% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for Compliance Inspection.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

***** **APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF** *****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____%

Total Cost _____

Attachment "B"
Guidelines, Specifications and Cost Summary

Work Write-Up
2018 0173

Haywood, Garry
768 Grosso Avenue
Macon, Georgia 31204
Home Phone: 478 254 4687 Cell Phone: 478 841 1325

Wednesday, May 9, 2018

Location

Prepared by: Sitten/Thurman

GENERAL REQUIREMENTS

01.0025 **Permits and Licenses**

Contractor shall obtain, pay for and post on site all permits and licenses necessary to complete this project. Contractor and subcontractors must have current licenses required by the State, County and City.

01. 0050 **Code Compliance**

All materials and methods of construction related to work performed on this project must comply with locally adopted code requirements and must meet with the approval of local code enforcement officials.

01. 0075 **Insurance Requirements**

The Contractor shall maintain such insurance as will protect him from claims for damages for personal injury, including death, which may arise from work performed on this project, whether such work be by himself or by any subcontractor or any one directly or indirectly employed by either of them. Contractor shall present Program Administrator with certificate of insurance evidencing comprehensive public liability insurance coverage not less than \$100,000/\$300,000 in the event of bodily injury including death and \$50,000/\$100,000 in the event of property damage arising out of the work performed by the Contractor. Worker's Compensation insurance if required by State law, Program Administrator or Homeowner.

01.0150 **Contractor to verify Measurements, Sizes and Quantities**

All measurements, sizes and quantities in this Work Write-Up are APPROXIMATE. The Contractor is responsible for verifying exact measurements, sizes and quantities prior to submitting a quote.

01.0200 **Workmanship and Material Standards**

Contractor to perform work specified in Work Write-Up in a high-quality good workman-like manner using specified materials or approved equals. Materials must: 1) be high quality, 2) be installed in accordance with manufacturer's specs and 3) meet requirements of code inspections.

01.0225 **General Warranty**

Materials installed and work performed shall have a one year Contractor warranty from the date of final acceptance of the work by the Homeowner & Program Administrator. Refer to project contract for specific requirements.

Attachment "B"
Guidelines, Specifications and Cost Summary

01.0250 **Scheduling Work**

Contractor to schedule work between 8:00am and 6:00pm, Monday through Friday. Requests to work before these hours and on weekends must be approved by the Homeowner and Program Administrator.

01.0275 **Compliance Inspections**

Contractor to call Program Administrator for inspection of all work that will be concealed from view following completion of work on that Item. Check each spec to see if a compliance inspection is required. Work concealed without an inspection may cause payment delays and denials.

01.0325 **Protect House Contents from Damage during Work**

Contractor shall take steps to protect house and contents from damage during project.

01.0350 **Repair Damage Caused to Property during Work**

Contractor is responsible for professionally repairing or replacing building and site components damaged as a result of construction activity.

01.0375 **Prime Bare Wood**

The exposed face of all newly installed wood and all wood scraped down to bare wood must be primed with appropriate primer.

01.0475 **Reduce Airborne Dust during Construction**

Contractor to take steps necessary to reduce and contain airborne dust created during construction, demolition and removal of defective paint. Wet scrape if removing defective paint. Do Not use electric sanders or torches to remove paint. Contractor and workers are encouraged to wear protective clothing and respirators and to follow hygiene procedures approved by OSHA.

01.0500 **GENERAL CLEANUP**

CONTRACTOR TO PROVIDE CLEAR AND SAFE PASSAGE WAYS IN AND AROUND STRUCTURE DURING PROJECT. CONTRACTOR TO REMOVE DEBRIS AND BUILDING MATERIALS FROM, IN AND AROUND STRUCTURE BEING REPAIRED TO LEGAL DUMP SITE REGULARLY AND AT THE END OF THE PROJECT.

Attachment "B"
Guidelines, Specifications and Cost Summary

35.0325 **Remove All Roof Covering Material down to Sheathing**

Remove all roof covering material down to roof sheathing or furring strips. Remove all debris to legal dump site. Take precautions to protect plants, shrubs, trees and fences from damage during removal.

35.0475 **Replace up to 30% of Roof Decking**

Replace up to 30% of any rotten, badly warped or broken roof decking and nailers. Material shall match remaining material as closely as possible. Call Program Administrator for compliance inspection before covering.

35.0925 **Install New Shingles on Roof Decking**

Install 15 lb. asphalt saturated felt and new 220 lb. or heavier Class A three tab fiberglass self-sealing strip shingles on top of roof decking using 8 nails per shingle. Install starter course at edges of roof. Shingles to have a 20 year limited manufacturer's warranty. Install metal flashing tucked behind siding at intersections of roof and walls. Install galvanized metal flashing tucked securely and at least 1/2" into masonry units of chimneys. Program Administrator will select color.

35.1075 **Install Ridge Vent**

Install continuous metal ridge vent along ridge lines of roof. Stop vents 18" from end of ridge line or from intersections of ridge lines. Make sure decking at ridge line is cut back at least 1" from edge of ridge pole so that the attic can ventilate.

*****APPLY DRIP EDGE AROUND THE PERIMETER OF THE ROOF*****

COST SUMMARY

Material – Labor _____

Overhead and Profit @ _____% _____

Total Cost _____