

This contract will be a \$100,000.00 contract that will run for two years or until the \$100,000.00 is expended. The low bidder will be established based on the bid quantity sheet totals. The Approximate Quantities are only for the purpose of the bid and do not reflect the quantities for the contract. Work Orders will be developed utilizing the unit costs shown in the bid quantity sheet.

Scope of Work

Contractors interested in providing Task Work Order Pavement Marking Services shall provide all materials, equipment, and labor necessary to perform Pavement Marking services as needed by Macon-Bibb County. The successful contractor shall be expected to perform services on the infrastructure described within this scope of work.

1. The work consists of the overspray of existing painted markings, or the removal of thermoplastic pavement markings and the application of new thermoplastic markings. The unit pricing shall consist of furnishing all labor, materials, and equipment necessary to complete the identified work area for various roadways throughout Macon Bibb County.
2. All work will be in accordance with the current GDOT specifications at the time of the issued Work Order, unless otherwise negotiated.
3. In all cases, the Macon Bibb Project Manager will describe the work, location and timing requirements involved. This will involve the Macon Bibb Project Manager providing a listing of the work to be completed through the issuance of a Work Order. This listing will include location information, such as addresses and/or site maps indicating the Pavement Marking locations.
4. The Contractor shall make efforts to prevent traffic from damaging and tracking of new pavement markings.

Work Schedule

1. Work Orders: This contract is for acquiring services for Task Work Order Pavement Marking Services. When this type of work is required to be performed within Macon Bibb's right-of-way and on public property, Macon Bibb will notify the Contractor to discuss the work that needs to be performed and receive a price for completing the work which will include labor, materials, equipment and mobilization.
2. Acceptance: The effective date of the work to be performed will be agreed upon by the Macon Bibb Project Manager and the Contractor. Should the Contractor decline multiple work requests, the Contractor could be removed from the list of Qualified Contractors for Macon Bibb County.

3. Notice to Proceed: The Work Order Notice to Proceed (NTP) will be issued in writing by the Macon Bibb Project Manager. Both parties shall mutually agree on the number of consecutive calendar days allowed to complete the work requested prior to the Contractor’s written acceptance of the Work Order. Should the work involve improvements that were not included in the bid, the Contractor shall submit a proposal for the work, and the Macon Bibb Project Manager shall approve of the proposal prior to work being performed. The Contractor shall perform the work and request a Macon Bibb representative to inspect the work and certify that the work is completed.

4. Period of Performance: The Period of Performance under this Contract shall commence upon the effective date of initial NTP. All work to be performed under this Contract shall be completed no later than two years for NTP, or as specified in the individual work order(s), whichever is sooner.

5. Invoices: Following completion of the work, the Contractor shall submit an invoice for the work completed. The costs shall reflect the prices received for the work order. No additional cost will be approved without prior authorization of the work. Macon Bibb will process the invoice for payment upon acceptance of the work performed.

Bid Quantities

Item Number	Item Description	Unit	Approximate Quantity	Unit Cost	Total Item Cost
	Waterborne High Build White and Yellow Traffic Line Paint				
1	Mobilization per Work Order	WO	10		
2	5 Inch Solid White or Yellow Painted Line	Linear Foot	1,200,000		
3	5 Inch Skip White or Yellow Painted Line	Gross Linear Foot	300,000		
4	8 Inch Solid White or Yellow Painted Line	Linear Foot	400		
	Thermoplastic				
5	5 Inch Solid White or Yellow Thermoplastic Line	Linear Foot	120,000		
6	5 Inch Skip White or Yellow Thermoplastic Line	Gross Linear Foot	30,000		
7	8 Inch Solid White or Yellow Thermoplastic Line	Linear Foot	1000		
8	24 Inch Solid White (Stop Bar)	Linear Foot	500		
9	Type 1 Pavement Marking Arrow (White)	Each	4		
10	Type 2 Pavement Marking Arrow (White)	Each	10		
11	Type 3 Pavement Marking Arrow (White)	Each	1		
12	Type 4 Pavement Marking Arrow (White)	Each	5		
13	Type 5 Pavement Marking Arrow (White)	Each	5		

14	Railroad Crossbuck	Each	6		
15	Bike (Bicycle) Lane Symbol	Each	15		
16	"ONLY" Word Symbol	Each	15		
17	"STOP" Word Symbol	Each	2		
18	Hatching, White; measurements include the 8 inch border and the areas within the borders	Square Yard	500		
19	Hatching Yellow; measurements include the areas within the borders and the 5 inch solid double yellow border	Square Yard	500		
20	Pedestrian Yield Lines, Layout Per MUTCD 38-16 and 38-17	Each			
21	Rumble strips, 20 ft. length per set (width will vary with the lane width), 3 sets of strips per lane per approach (GDOT Specs, 270 mil thickness)	Per Approach	5		
	Miscellaneous				
22	Removal of Each Type of Line	Linear Foot	500		
23	Removal of Hatching	Square Yard	50		
24	Removal of "ONLY" Symbol	Each	1		
25	Removal of "STOP" Symbol	Each	1		
26	Furnish and install raised pavement markers (Stimsonite Model 88 (or approved equivalent) white or yellow to match line type and application.	Each	1000		

Total Bid Quantity: _____