



Macon-Bibb County Government

Procurement Department

City Hall

700 Poplar Street, Suite 308

Macon, Georgia 31201

(478) 803-0550

Fax (478) 751-7252

Laura Hardwick
Director of Procurement

February 14, 2025

ADDENDUM # 1

To: ALL PROSPECTIVE FIRMS

Re: INVITATION FOR BIDS: 25-030-LH, Deep Patch with Asphalt Resurfacing Projects

The Invitation for Bids, referenced above, is modified as follows:

1. What will be the allowed work hours on this project?

Answer: Normal work hours, 8-5 or as light permits.

2. Will the contractor be required to post mount the advanced warning signs or can these signs be placed on a tripod stand?

Answer: Advance warning signs may be placed on tripod.

3. How long will a milled roadway be allowed to remain without the finished asphalt layer?

Answer: Final repaving should be completed within one day of the milling work.

4. Will the contractor be required to mill and pave into the side roads?

Answer: Mill and pave, at the side road intersection, through the side road end of the curb radius.

5. Will the contractor be required to mill and pave any driveways?

Answer: No driveway paving is included.

6. On the Bid Schedule several line items have a zero quantity. Should the contractor place an N/A for the Unit Price and Total for that line item? Please clarify.

Answer: Any zero quantity items may be answered with N/A. Please see attached revised Road List and Quantities which is labeled Attachment C.

7. Can Macon Bibb issue a spec for adjusting the manholes and water valves?

Answer: Contact the Macon Water Authority for requirements for adjustments to manholes and water valves.

8. Dora St. and Azalea Dr. both a drainage grate that will need to be adjusted after the final asphalt. Will a pay item be added for this adjustment – please advise?

Answer: No grate adjustment should be needed. Just mill out 1.25 inches, then put back 1.25 inches.

9. Will the finished asphalt need to be flushed with the lip of the curb and gutter?

Answer: Mill out the existing asphalt 1.25 inches, then put back 1.25 inches.

10. Dora St. has parking spaces on the left closest to the ball field. Will this area be milled and paved?

Answer: Mill out and repair the two through lanes, parking spaces are not included.

11. Will the mill and pave section of Bass Rd. tie into the limits of the new bridge construction on Bass Rd.?

Answer: The St. Croix Drive intersection is the south end of your Bass Road work.

12. Goodall Mill Rd. has existing thermoplastic rumble strips on it. Will these thermoplastic rumble strips be replaced – if so, a pay item is needed?

Answer: A lump sum pay item for all Goodall Mill Road rumble strips will be added to the bid quantities by addendum.

13. Will Macon Bibb consider changing the Quantity and Unit of Patching to tons?

Answer: Bid patching as shown.

14. What will be the depth of the Milling?

Answer: Mill depth is 1.25 inches.

15. It looks like the Milling will be full width curb to curb – is this correct?

Answer: Milling is from lip of curb to lip of curb.

16. What will the depth of the Patching be?

Answer: Milling for patching to a depth to remove cracking as needed, maximum four inches deep.

17. Will 19mm be used for the Patching?

Answer: All mixed places for this project is 9.5 mm asphalt.

18. It looks like the depth of the 9.5mm will be 1.25" - is this correct?

Answer: Yes.

19. What type 9.5mm will be required on this project – Type 1 or Type 2?

Answer: Type 1

Please incorporate this change into the Invitation for Bid and acknowledge receipt of this addendum on your bid form.

Sincerely,

Laura Hardwick

2023 LMIG – BID TWO ROADS LIST

Road Name	From-To	Length (Miles)
Summerwind Drive	Silver Springs Drive – Springdale Woods Drive	0.09
Summerwind Drive	Fawn Lake Court – Oak Tree Drive	0.06
Bass Road	St. Croix Drive – Yeomans Drive (527 Ft. North)	0.10
Sherwood Drive	Canton Street – Dove Street	0.06
Sherwood Drive	College Street – College Drive	0.06
Azalea Drive	ClubTrace – Greenfields Road	0.03
Dorchester Court	Kimmeridge Drive – Dorchester Court	0.08
Drury Drive	Robert Place – Roycrest Drive	0.09
Jordan Drive	Northlake Drive – Jordan Drive Cul-De-Sac	0.07
Dixon Road	Dixon Road – Fulton Mill Road	0.07
Camellia Street	Pansy Avenue – Poppy Avenue	0.05
Blossom Avenue	Mercer University Drive – Daffodil Street	0.05
Harris Street	Pio Nono Avenue – Adams Avenue	0.10
Crawford Street	Pio Nono Avenue – Dent Street	0.23
Winton Avenue	Montpelier Avenue – Cherry Avenue	0.10
Dora Street	Cedar Avenue – Marigold Avenue	0.02
Anthony Circle	Anthony Terrace – Anthony Terrace	0.21
Beech Avenue	Brentwood Avenue – Winton Avenue	0.09
Villa Crest Avenue	Flamingo Drive – San Juan Avenue	0.13
Villa Crest Avenue	Houston Avenue – San Juan Avenue	0.08
Robert Henry Street	Sharl Street – Harrell Street	0.08
Heard Avenue	Houston Avenue – Sharl Street	0.09
Hanson Street	Bacon Street – Simmons Street	0.08

Moreland Avenue	San Juan Avenue – Flamingo Drive	0.13
Charleston Circle	Kingsbury Drive – Charleston Circle	0.07
Carlisle Avenue	Fairburn Avenue – Napier Avenue	0.12
Goodall Mill Road	Sardis Church Road – Houston Road	1.24
Bradstone Circle	Millerfield Road – Bradstone Circle	0.07
Bradstone Circle	Bradstone Circle – Bradstone Court	0.24
Wrenwood Drive	Woodcrest Road – Larkwood Drive	0.08
Stallings Drive	Bloomfield Road – Stallings Drive	0.07

2023 LMIG Projects for Macon-Bibb County

(Roadway Repair and Resurfacing)

Bid Schedule – BID TWO

The quantities listed are an approximate estimate of the materials required to complete the roadway repair and resurfacing projects, for the Main Streets list. The “Total Bid Price” is the bid amount which shall be used to award the 2023 LMIG – BID TWO paving contract to the successful bidder.

Prior to beginning contract paving work on the main streets, the successful bidder shall be required to contact Mike Beard with the Macon Water Authority, at (478) 256-9382, regarding coordination with MWA on locating /marking paved over sanitary manholes. Contact Willie Sidney with the Macon Water Authority, at (478) 256-9400, to locate / mark paved over water valves.

Also, the successful bidder shall contact Monte Tolleson with the Macon Water Authority Storm Water Office, at (478) 738-6520, regarding locating / marking paved over storm manholes.

The 150-day contract period shall proceed upon the successful bidder receiving the “Notice to Proceed” from our Procurement Office.

PROJECT BID: (MILLING, PATCHING AND RESURFACING):

Main Streets – Summerwind Drive, Summerwind Drive, Bass Road, Sherwood Drive, Sherwood Drive, Azalea Drive, Dorchester Court, Drury Drive, Jordan Drive, Dixon Road, Camellia Street, Blossom Avenue, Harris Street, Crawford Street, Winton Avenue, Dora Street, Anthony Circle, Beech Avenue, Villa Crest Avenue, Villa Crest Avenue, Robert Henry Street, Heard Avenue, Hanson Street, Moreland Avenue, Charleston Circle, Carlisle Avenue, Goodall Mill Road, Bradstone Circle, Bradstone Circle, Wrenwood Drive, Stallings Drive

<u>Quantity</u>	<u>Unit</u>	<u>Item</u>	<u>Unit Price</u>	<u>Total</u>
3,741	TONS	Milling	_____	_____

3,277	GAL	Bituminous Tack	_____	_____
5,462	SY	Roadway Patching	_____	_____
3,741	TONS	9.5 mm Superpave Asphalt	_____	_____
240	EA	Install Furnished Sewer Manhole & Water Valve Risers, 1"	_____	_____
0	CY	GABC Stab. Subgrade	_____	_____
0	EA	Traffic Control Loops	_____	_____
1.95	MILES	Striping (Paint)	_____	_____
0	EA	Pavement Markings (Arrows, Thermoplastic)	_____	_____
389	LF	Pavement Markings (X- Walks, Thermo)	_____	_____
127	LF	Pavement Markings (Stop Bars, Thermoplastic)	_____	_____
0	LF	Pavement Markings (Hatching, Thermoplastic)	_____	_____
0	EA	Bike Symbols (Thermoplastic)	_____	_____
0	EA	Railroad Symbols (Thermoplastic)	_____	_____

130	EA	Manholes (Adjust)	_____	_____
110	EA	Water Valves (Adjust)	_____	_____
0	EA	“Only” Symbol (Fifth Street) (Thermoplastic)	_____	_____
1.35	MILES	Raised Pavement Markers	_____	_____
All	LS	Goodall Mill Road Rumble Strips	_____	_____
2.98	Miles	Grass Shoulder Road Edge Clipping	_____	_____

Total Bid Price _____