

Pave the Way Package 3 for Macon-Bibb County

(Roadway Repair and Resurfacing)

Bid Schedule – Pave the Way Package 3

The quantities listed are an approximate estimate of the materials required to complete the roadway repair and resurfacing projects, for the Main Streets list. The “Total Bid Price” is the bid amount which shall be used to award Pave the Way Package 3 paving contract to the successful bidder.

Prior to beginning contract paving work on the main streets, the successful bidder shall be required to contact Mike Beard with the Macon Water Authority, at (478) 256-9382, regarding coordination with MWA on locating /marking paved over sanitary manholes. Contact Willie Sidney with the Macon Water Authority, at (478) 256-9400, to locate / mark paved over water valves.

Also, the successful bidder shall contact Monte Tolleson with the Macon Water Authority Storm Water Office, at (478) 738-6520, regarding locating / marking paved over storm manholes.

The 120-day contract period shall proceed upon the successful bidder receiving the “Notice to Proceed” from our Procurement Office.

| <u>Road Name</u> | <u>From</u> | <u>To</u> | <u>Miles</u> |
|--------------------------|-------------------|--|--------------|
| Goodall Mill Rd | Jones Rd | Sardis Church Road | 1.01 |
| Guy Paine Rd | Pio Nono Ave | MLK | 0.52 |
| Allied Industrial | End of Rd | Mead Rd | 0.65 |
| Old Gaull City Rd | Allied Industrial | To a Point 212 Ft South of the RR Crossing | 0.28 |
| Allen Rd | Houston Rd | Hawkinsville Rd | 1.09 |
| Allen Rd | Hawkinsville Rd | East of 2104 Allen Rd | 0.33 |
| General Winship | Pinecrest Rd | General Winship Dr S | 0.29 |
| General Winship South | General Winship | Ingleside Ave. | 0.14 |
| Pinecrest Rd | Old Holton Rd | Elmridge Dr | 0.41 |
| Rogers Dr | End of Drive | Kingsley Dr | 0.22 |
| Corbin Ave | Riverside Dr | Old Holton Rd | 0.48 |
| Old Holton Rd | Pierce Ave | Corbin Ave | 0.44 |
| Thurmond Dr | Nancelon Cir N | Old Holton Rd | 0.26 |
| Newton Pl | End of Rd | Thurmond Dr | 0.04 |
| Kingsley Dr | Walton Pl | Rockbridge Rd | 0.09 |
| Rockbridge Rd | Adrian Pl | Kingsley Dr | 0.10 |
| Adrian Pl | Motes Pl | End of Rd | 0.25 |
| Walton Pl | Adrian Pl | Motes Pl | 0.05 |
| Motes Pl | End of Rd | Walton Pl | 0.18 |
| | | | 6.85 |

Pave the Way Package 3

| Item | Unit | Quantity | Unit Price | Total |
|---|------|----------|------------|-------|
| Milling | TONS | 8124.0 | | |
| Bituminous Tack | GAL | 5908.35 | | |
| Roadway Patching | SY | 9847.24 | | |
| 12.5 mm Superpave Asphalt | TONS | 8124.0 | | |
| 9.5 mm Superpave Asphalt | TONS | 0 | | |
| Install Furnished Sewer Manhole, Storm Manholes, | EA | 113 | | |
| Install Furnished Water Valve Riser | EA | 79 | | |
| Manhole (Adjustment) | EA | 113 | | |
| Water Valve (Adjustment) | EA | 79 | | |
| Traffic Signal Loop Install | EA | 9 | | |
| Striping (Center Lines, Edge Lines, Lane Lines) | LF | 92948 | | |
| Painted Arrows | EA | 10 | | |
| Bike Symbols | EA | 0 | | |
| Painted Messages | EA | 0 | | |
| Painted Crosswalks | LF | 356 | | |
| Painted Stop Bars | LF | 320 | | |
| Painted RR Symbols | EA | 0 | | |
| Painted Hatching | LF | 40 | | |
| Rumble Stripe | SET | 0 | | |
| RPMs | MILE | 6.85 | | |
| Clipping Grassed Shoulders | MILE | 6 | | |

Total Bid \$ _____