

**Pave the Way Package 4  
for Macon-Bibb County  
(Roadway Repair and Resurfacing)  
Bid Schedule – Pave the Way Package 4**

**The quantities listed are an approximate estimate of the materials required to complete the roadway repair and resurfacing projects, for the Main Streets list. The “Total Bid Price” is the bid amount which shall be used to award Pave the Way Package 4 paving contract to the successful bidder.**

**Prior to beginning contract paving work on the main streets, the successful bidder shall be required to contact Mike Beard with the Macon Water Authority, at (478) 256-9382, regarding coordination with MWA on locating /marking paved over sanitary manholes. Contact Willie Sidney with the Macon Water Authority, at (478) 256-9400, to locate / mark paved over water valves.**

**Also, the successful bidder shall contact Monte Tolleson with the Macon Water Authority Storm Water Office, at (478) 738-6520, regarding locating / marking paved over storm manholes.**

**The 120-day contract period shall proceed upon the successful bidder receiving the “Notice to Proceed” from our Procurement Office.**

<u>Road Name</u>	<u>From</u>	<u>To</u>	<u>Miles</u>
<b>Lamar Rd</b>	Zebulon Rd	Runnymede Ln	1.80
<b>Peake Rd</b>	Plantation Way	Zebulon Rd	0.34
<b>Peake Rd</b>	Zebulon Rd	Plantation Inn Dr North	0.10
<b>Peake Rd</b>	Plantation Inn Dr (South)	I-475	0.69
<b>Plantation Inn Dr. North</b>	Plantation Inn Dr South	Peake Rd	0.06
<b>Tharpe Dr</b>	Wesleyan Dr	Northside Dr	0.44
<b>Maplewood Dr</b>	Tharpe Dr	Leo Pl	0.41
<b>Savage Creek Dr</b>	Maplewood Dr	Marlowe Dr	0.28
<b>Savage Hills Dr</b>	Maplewood Dr	Marlowe Dr	0.27
<b>N Beechwood Dr</b>	Glenwood Dr	Glenwood Dr	0.58
<b>Glenwood Dr</b>	Maplewood Dr	N Beachwood Dr	0.06
<b>Glenwood Dr</b>	Marlowe Dr	Forest Hill Rd	0.34
<b>Cheryle Ann Dr</b>	Wesleyan Dr	Maplewood Dr	0.32
<b>Leo Pl</b>	Cheryle Ann Dr	Maplewood Dr	0.30
<b>Sprucewood Dr</b>	S Beechwood Dr	Marlowe Dr	0.27
<b>N Stratford Oaks Dr</b>	Maplewood Dr	Marlowe Dr	0.27
<b>S Stratford Oaks Dr</b>	Maplewood Dr	Marlowe Dr	0.27
<b>Wilshire Dr</b>	S Stratford Oaks Dr	Timberlane Dr	0.07
<b>Timberlane Dr</b>	Wesleyan Dr	Marlowe Dr	0.63
<b>Hathaway Dr</b>	Timberland Dr	End of Road	0.13
<b>Lattimore Dr</b>	Hathaway Dr	Marlowe Dr	0.36
			7.99

## Pave the Way Package 4

Item	Unit	Quantity	Unit Price	Total
Milling	TONS	9964.8		
Bituminous Tack	GAL	7247.15		
Roadway Patching	SY	12078.58		
12.5 mm Superpave Asphalt	TONS	9964.8		
9.5 mm Superpave Asphalt	TONS	0		
Install Furnished Sewer Manhole, Storm Manholes,	EA	114		
Install Furnished Water Valve Riser	EA	46		
Manhole (Adjustment)	EA	114		
Water Valve (Adjustment)	EA	46		
Traffic Signal Loop Install	EA	6		
Striping (Center Lines, Edge Lines, Lane Lines)	LF	71240		
Painted Arrows	EA	38		
Bike Symbols	EA	0		
Painted Messages	EA	3		
Painted Crosswalks	LF	336		
Painted Stop Bars	LF	574		
Painted RR Symbols	EA	0		
Painted Hatching	LF	256		
Rumble Stripe	SET	6		
RPMs	MILE	7.99		
Clipping Grassed Shoulders	MILE	4.61		

**Total Bid \$** \_\_\_\_\_